BRUHAT BANGALORE MAHANAGARA PALIKE
Yelahanka Zone, Electrical Division

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name of work :- Providing LED Street lights/Control switches/control wires at Dark/vulnerabale places in Ward no 01,02,03 & 04.

Sl. No	Qty	Description Of Work	Unit	Quoted Rates	In figures
1	1150	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material. delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 Housing with supplier word mark /name shall be Engraved / bossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source.LED Streetlight 90 Watts	Nos	7514.42	Rupees Seven Thousand Five Hundred Fourteen And Paise Forty Two Only
2	1127	Supplying and Fixing of mm dia class A GI pipe bracket up to 2 Mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires.Using 32mm dia G.I.Pipe	Each	876.33	Rupees Eight Hundred Seventy Six And Paise Thirty Three Only
3	1150	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires.	Each	183.66	Rupees One Hundred Eighty Three And Paise Sixty Six Only
4	4000	Wiring for lighting/power circuit using one of PVC insulated 1100V grade, stranded Aluminium wire single core in open or concealed system of wiring.4 sqmm	Mtrs	9.44	Rupees Nine And Paise Forty Four Only
5	55	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) 100Amps 25kA.	Each	4754.23	Rupees Four Thousand Seven Hundred Fifty Four And Paise Twenty Three Only
6	55	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop- Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/ Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.260mmx210mmx116mm	Each	2155.67	Rupees Two Thousand One Hundred Fifty Five And Paise Sixty Seven Only

For M/s. Suraksha Electricals

Proprietor

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

7	600	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1. Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 4 core 16 sqmm	Mtrs	157.42	Rupees One Hund Fifty Seven And Pa Forty Two Only
8	600	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.On wall /Structure 6 sqmm to 16 sqmm	Mtrs	31.48	Rupees Thirty One And Paise Forty Eight Only
9	40	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.300mmx450mmx214mm	Each	5380.78	Rupees Five Thousand Three Hundred Eighty And Paise Seventy Eigh Only
10	40	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.50-63 Amps SP	Each	758.78	Rupees Seven Hundre Fifty Eight And Paise Seventy Eight Only
11	40	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947 100 to 125Amps	Each	7556.40	Rupees Seven Thousar Five Hundred Fifty Six And Paise Forty Only
12	40	Supplying, fixing and wiring rotary selector switch suitable for Voltmeter (Togal switch)	Each	141.68	Rupees One Hundred Forty One And Paise Sixty Eight Only
13	16	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required.25x3mm GI strip	Mtrs	78.71	Rupees Seventy Eigh And Paise Seventy On Only
14	20	Wiring for lighting/power circuit using one of **FRLS** PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.6 sqmm	Mtrs	73.46	Rupees Seventy Thre And Paise Forty Six On
15	200	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.6 sqmm	Each	7.35	Rupees Seven And Paise Thirty Five Onl
16	4	Supply of RCC Pole - 9 Mtr Long, 145 Kg WL (Dwg No.BESCOM/GM/QS&S/02 Dtd 24.11.2018) as per IS-785	Nos	6567.77	Rupees Six Thousand Five Hundred Sixty Seven And Paise Seventy Seven Only
17	4	Digging of Pits 1.8 mtr depth for errection of 9 to 10 mtr Long Steel/RCC/PSC supports as per approved Drawing. 1)Ordinary Soil	Per Pit	436.59	Rupees Four Hundre Thirty Six And Paise Fi Nine Only
18	4	Supply of LT 2 Pin X Arms - MS (Dwg No. BESCOM/GM/QS&S/32 Dtd 24.11.2018)	Nos	91.30	Rupees Ninety One A Paise Thirty Only
19	4	Erection of steel supports 9.0 to 10.00 mtr long such as 22.68 kg (50 lbs) Rail, 27.22 kg (60 Lbs) Rail I Beam of sizes 200x100mm, 175x90 mm, 125x100 mm. Fabricates poles tubular poles in pits of 1.8 mtr Depth, Aligning, Refilling with soil and ramming as approved drawing	Nos	350.53	Rupees Three Hundre Fifty And Paise Fifty Three Only

For M/s. Suraksha Electricals

Proprietor

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

20	4	1.1 kV, LT Aerial Bunched Cable, confirming to IS-14255: 1995 XLPE insulation Parameter shall be as below 1. Hot Set Test: a) Elongation under Load: 50% (Max) b) Permanent Elongation After Cooloing: 3% (Max) 2. Thermal Aging in oven: a) Tensile Strength: 16 N/mm² (Min) b) Elongation: 375% (Min) 3. Water Absorption Test a) Water absorbed: 0.5 mg/cm² (Max) 4. Carbon Black Content shall be ranging from 2% to 3% 3x25 + 1x25 + 1x16 Sqmm Street light (Insulated Messenger cum Neutral)	KM	154276.50	Rupees One Lakh(s) Fifty Four Thousand Two Hundred Seventy Six And Paise Fifty Only
21	4	Stringing of 1.1 kV grade Aerial Bunched 3 Core cable of XLPE insulation of size (3x95) (Phase Conductor) + (1x70) (Insulated Messenger Neutral) + (1x25) (Street Light Control)	KM	23581.22	Rupees Twenty Three Thousand Five Hundred Eighty One And Paise Twenty Two Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For M/s. Suraksha Electricals

Contractor

Proprietor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone